

DES Advisory Board Meeting Second Quarter FY15 March 5, 2015



Agenda

- 1. Call to Order
- 2. Review & Approval of Previous Meeting Minutes
- 3. Customer Sales
- 4. Review of DES Contractor Performance
- 5. Natural Gas Purchasing Status
- Natural Gas Curtailment
- 7. FY15 Costs to Date
- 8. Capital Projects Review & Status
- 9. DES Combined Heat and Power Project
- 10. Other Board Member Items
- 11. Adjourn



1. Call to Order

2. Review and Approval of Previous Meeting Minutes



3. Customer Sales

- Table 3A: Customer Cost Comparison
- Figure 3A: Historic Customer TIFS
- ❖ Table 3B: Historic Customer TIFS Summary
- ❖ Figure 3B: Historic System Delta T

Metro Nashville DISTRICT ENERGY SYSTEM

Summary Table 3A: Customer Cost Comparison for the Previous 12 Months

		Steam - Rolling 12 Month		Chilled Water - Rolling 12 Month			
		Jan 2013 - Dec 2013	Jan 2014 - Dec 2014	% Diff.	Jan 2013 - Dec 2013	Jan 2014 - Dec 2014	% Diff.
Private	Cost	\$ 1,360,721	\$ 1,560,909	14.71%	\$ 3,301,911	\$ 3,418,326	3.53%
	Usage (lbs or tonhrs)	91,310,531	94,403,874	3.39%	17,326,547	16,874,237	-2.61%
	Unit Cost	\$ 14.90	\$ 16.53	11.0%	\$ 0.191	\$ 0.203	6.3%
State	Cost	\$ 1,917,956	\$ 2,211,669	15.31%	\$ 3,332,261	\$ 3,315,912	-0.49%
	Usage (lbs or tonhrs)	116,908,202	122,481,519	4.77%	16,027,536	14,285,716	-10.87%
	Unit Cost	\$ 16.41	\$ 18.06	10.1%	\$ 0.208	\$ 0.232	11.6%
Metro	Cost	\$ 2,447,347	\$ 2,822,225	15.32%	\$ 5,109,691	\$ 5,559,240	8.80%
	Usage (lbs or tonhrs)	187,820,650	185,965,300	-0.99%	30,443,759	28,799,790	-5.40%
	Unit Cost	\$ 13.03	\$ 15.18	16.5%	\$ 0.168	\$ 0.193	15.0%
Aggregate	Cost	\$ 5,762,111	\$ 6,727,020	16.75%	\$11,743,863	\$12,403,034	5.61%
	Usage (lbs or tonhrs)	397,524,127	408,785,823	2.83%	63,797,842	60,547,663	-5.09%
	Unit Cost	\$ 14.49	\$ 16.46	13.5%	\$ 0.184	\$ 0.205	11.28%



Figure 3A: Historic Customer TIFS







Table 3B: Historic Customer TIFS Summary

	FY07	FY08	FY09	FY10	FY11	FY12	FY13	FY14	FY15	Cumulative
State TIFS	\$13,997	\$ 52,421	\$53,165	\$ 56,182	\$ 68,228	\$ 65,471	\$ 66,074	\$ 45,327	\$33,720	\$ 454,584
Metro TIFS	\$ 7,061	\$ 22,810	\$25,188	\$ 30,929	\$ 36,007	\$ 35,969	\$ 35,496	\$ 28,873	\$18,375	\$ 240,708
Private TIFS	\$ 4,912	\$ 31,830	\$21,022	\$ 18,318	\$ 24,372	\$ 29,201	\$ 46,829	\$ 39,558	\$13,542	\$ 229,584
Totals	\$25,970	\$107,061	\$99,374	\$105,429	\$128,607	\$130,641	\$148,399	\$113,757	\$65,637	\$ 924,875
State TIFS	54%	49%	53%	53%	53%	50%	45%	40%	51%	49%
Metro TIFS	27%	21%	25%	29%	28%	28%	24%	25%	28%	26%
Private TIFS	19%	30%	21%	17%	19%	22%	32%	35%	21%	25%
Totals	100%	100%	100%	100%	100%	100%	100%	100%	100%	100%



Figure 3B: Historic System Delta T






4. Review of DES Contractor Performance

Contractor (CNE) is in compliance with their contractual obligations for FY15.

- Excellent Performance No Improvement Necessary
- Satisfactory Performance Some Improvement Could Be Made
- Poor Performance Much Improvement Necessary




Performance Measurement FY15: Steam Electric Conversion






Performance Measurement FY15: Steam Plant Efficiency






Performance Measurement FY15: Steam Water Conversion






Performance Measurement FY15: CHW Electric Conversion





Performance Measurement FY15: CHW Water Conversion





Water Treatment

- Steam and Condensate
 - Corrosion
 - ❖ Iron
 - Hardness
 - Chlorine/Sulfite
- Condensing Water
 - Conductivity
 - Biologicals
- Chilled Water
 - ❖ Hardness
 - Corrosion
 - ❖ Biologicals
 - ❖ Delta T Issue



EGF Walkthrough

- ✓ Equipment Maintenance
- ✓ Operations
- ✓ Electrical
- ✓ Housekeeping
- ✓ Building Structure ■
- ✓ Building Exterior and Grounds ●



EDS Walkthrough

- ✓ Vault/Tunnel Housekeeping
- ✓ Maintenance Items
 - ✓Insulation Repair/Replacement
 - ✓ Water Infiltration
 - ✓ Corrosion of Structural Metal Components
- √ Safety Items



5. Natural Gas Purchasing

- Natural Gas Purchasing Review
 - ❖Table 5: FY15 Gas Spending & Budget Comparison
 - Figure 5: Actual and Projected Gas Cost Comparison



Table 5: FY15 Gas Spending & Budget Comparison


	To d	Actual FY15 late (Dec 31)	Budget FY15	Percent Difference
Steam Sendout (Mlbs)		199,432	189,497	5.0%
Fuel Use (Dth) (includes propane)		273,769	263,211	4.0%
Plant Eff (Dth/Mlb)		1.372	1.389	-1.2%
Total Gas Cost (includes propane)		\$1,318,016	\$1,289,997	2.2%
Unit Cost of Fuel (\$/ Dth)		\$4.814	\$4.901	-1.8%

Excludes consultant fees and FEA and budget contingency;

Includes transportation and propane costs



Figure 5. Actual and Projected Gas Cost Comparison History





6. Natural Gas Curtailment

- Piedmont Natural Gas Company notified CNE at 9:00 am Tuesday January 6, 2015 of an upcoming gas curtailment
- Anticipated Curtailment Period:
 - > 9:00 am Wednesday January 7, 2015 9:00 am Friday January 9, 2015
- Storage Tank
 - > Capacity: 18,000 Gallons
 - Maximum Fill Level: (80%) 14,400 Gallons
- Anticipated Usage
 - > Burn Rate: 2,000 gallons per hour
 - Propane Heat Value = 91,000 BTU per gallon
 - > 182 DECATHERMS/HOUR
 - Full Storage Tank = 6.5 Hours
- > Transport
 - > Tanker Truck Capacity: 9,300 gallons



Propane System



UNDERGROUND STORAGE TANK



VAPORIZER



BOILER



Propane Delivery Schedule

	Deliveri	es (Gal)		Tank Le	evel (Gal)	
	<u>Scheduled</u>	<u>Actual</u>	<u>Befo</u>	<u>ore</u>	<u>Afte</u>	<u>er</u>
Tuesday January 6, 2015						
5:00 PM	2700	2920	12,150	67.5%	15,066	83.7%
Wednesday January 7, 2015						
7:00 AM		Swap Bo	oilers to Propane			
9:00 AM		Curtai	lment Begins			
2:00 PM	9300	9300	2,466	11.2%	11,920	66.2%
7:00 PM	9300	9199	2,920	16.2%	12,119	67.3%
12:00 AM	9300	9304	3,119	17.3%	12,423	69.0%
Thursday January 8, 2015						
5:00 AM	9300	9344	3,423	19.0%	12,767	70.9%
10:00 AM	9300	9304	3,767	20.9%	13,071	72.6%
3:00 PM	9300	9329	4,071	22.6%	13,400	74.4%
8:00 PM	9300	9304	4,400	24.4%	13,704	76.1%
Friday January 9, 2015						
1:00 AM	9300	9329	4,704	26.1%	14,033	78.0%
6:00 AM	9000	9005	5,033	28.0%	14,038	78.0%
9:00 AM		Curta	ilment Ends			
10:00 AM	9000	9000	4,950	27.5%	13,950	77.5%



Propane Usage and Costs

	Deliveries (Gal)	Unit Cost	Cost	Vendor
Tuesday January 6, 2015				
5:00 PM	2,920	\$ 0.91	\$ 2,642.87	Advanced
Wednesday January 7, 2015				
2:00 PM	9,300	\$ 0.91	\$ 8,417.37	Advanced
7:00 PM	9,199	\$ 0.88	\$ 8,109.84	Targa
12:00 AM	9,304	\$ 0.88	\$ 8,202.40	Targa
Thursday January 8, 2015				
5:00 AM	9,344	\$ 0.88	\$ 8,237.67	Targa
10:00 AM	9,304	\$ 0.88	\$ 8,202.40	Targa
3:00 PM	9,329	\$ 0.88	\$ 8,224.44	Targa
8:00 PM	9,304	\$ 0.88	\$ 8,202.40	Targa
Friday January 9, 2015				
1:00 AM	9,329	\$ 0.88	\$ 8,224.44	Targa
6:00 AM	9,005	\$ 0.88	\$ 7,938.81	Targa
10:00 AM	9,000	\$ 0.88	\$ 7,934.40	Targa
Gallons Purchased	95,338		\$ 84,337.06	
Beginning Inventory	12,150	\$ 2.89	\$ 35,070.49	
	107,488		1	
Remaining Inventory	13,950			
Propane Used	93,538	\$ 1.11	\$ 103,909.83	= \$12.21/Dth
		(weighted average)		

24



7. FY15 Costs to Date

Item				Percent
	FY14 Actual	FY15 Budget	FY15 Actual	of
			to date	FY15 Budget
FOC's	\$ 4,459,927	\$ 4,533,300	\$ 2,266,038	49.99%
Pass Throughs				
Non-Energy	\$ 1,082,270	\$ 1,187,267	\$ 749,119	63.10%
Water/Sewer	\$ 485,337	\$ 721,800	\$ 311,472	43.15%
Natural Gas Base	\$ 3,354,335	\$ 2,972,673	\$ 1,289,992	43.40%
Natural Gas Contingency	\$ -	\$ 635,260	\$ 28,024	4.41%
Electricity	\$ 5,225,956	\$ 6,576,100	\$ 3,276,845	49.83%
Debt Service	\$ 5,705,732	\$ 5,491,800	\$ 3,089,859	56.26%
Total Expenses	\$20,313,558	\$22,118,200	\$ 11,011,349	49.78%
Total Revenues	\$18,396,977	\$20,268,500	\$ 9,814,029	48.42%
Metro Funding Amount	\$ 1,916,581	\$ 1,849,700	\$ 924,850	50.00%



8. Capital Expenditure Update

	Spent to End of FY14	FY15 Spending	Balance to Date (01/19/15)
R&I Projects	\$2,293,259	\$29,699	\$321,101
49109-2010 Bond	\$1,891,257	\$10,996	\$723,663
49107-Customer Connection Fund	\$6,575,530	\$44,716	\$1,886,682
Total	\$10,760,046	\$85,411	\$2,931,446



Capital Projects Review

Active Capital Projects

- DES 061: MH & Tunnel Steel Corrosion Repair & Prevention ongoing
- DES 089: AA Birch Tunnel Repairs
- DES 104: TOU developing TOU invoicing changes
- DES 105: Vertical Tunnel Shaft Repairs at Suntrust Building
- DES 106: MCH Chilled Water Mods awaiting Phase II
- DES 107: West Riverfront Park Manhole Repairs
- DES 108: 7th Avenue Tunnel Insulation Repairs
- DES 109: Indigo Hotel Sparge Tube
- DES 110: EGF Alternate Fuels Evaluation
- DES 111: EGF Combined Heat and Power



Capital Projects Review

Capital Projects in Close-out

- DES 089: AA Birch Tunnel Repairs
- DES 105: Vertical Tunnel Shaft Repairs at Suntrust Building




9. DES Combined Heat and Power

- 1. Provides Approximately 7,000 kW of Self-generated Electricity
- 2. Provides 150,000 pph of Additional Steam
- 3. Provides 1,500 tons of Additional Chilled Water
- 4. Improves DES Efficiency
- 5. Annual Operating Savings of \$2,450,000 to DES Customers with Net 6.2% Average Annual Savings
- 6. Provides Triple Electrical Redundancy to Riverfront Flood Mitigation Project
- 7. Approximately \$18 million in Net Capital Cost
- 8. Less Than 8 Year Simple Return on Investment




CHP Flow Diagram





CHP Electric Flow Diagram





10. Other Board Member Items



11. Adjourn

- > Advisory Board Meeting Schedule
- > FY15 3rd Quarter Meeting May 21, 2015
- > FY15 4th Quarter Meeting August 20, 2015
- > FY16 1st Quarter Meeting November 19, 2015
- > FY16 2nd Quarter Meeting February 18, 2016